GHXTox: Peptide toxicity prediction by fusing a task-adaptive protein language model with pLDDT-aware multi-scale 3D structural modeling

LaLaLa, LaLaLa, LaLaLa, LaLaLa

Abstract

Peptide toxicity is a major safety concern in peptide-based drug development, motivating accurate computational screening methods. Existing methods have begun to explore multi-dimensional (multimodal) feature fusion and toxicity prediction based on the three-dimensional (3D) conformations of peptides, yet most of them still underutilize 3D structural information, and systematic multi-dimensional fusion remains rare. Here, we propose GHXTox, a hierarchical dual-level fusion framework in which a 3D structural expert first integrates sequence semantics with spatial structural features through predicted local-distance difference test (pLDDT)-aware cross-attention, and is then fused at the probability level with a task-adaptive one-dimensional (1D) sequence expert using weights frozen on training out-of-fold (OOF) predictions. The 1D branch analyzes sequences with a protein language model (ProtT5 fine-tuned with low-rank adaptation, LoRA) and a bidirectional Mamba state-space model. The 3D expert integrates an ESMFold-derived structural anchor, pLDDT-aware residue geometry, and full-atom-derived chemical sites. Multi-conformer information is retained only in training-side representation learning and controlled ablations; benchmark and public inference always use the single-structure base logits. On the frozen historical benchmark test sets, GHXTox achieves MCC values of 0.8705 and 0.6673 and AUPRC values of 0.9674 and 0.8046 on Test1 and Test2, respectively. Further analyses characterize residue-level sequence sensitivity, confidence–gate associations, chemical-site perturbations, expert disagreement, and an OOF-frozen selective-prediction rule. At realized coverages of 88.54% and 86.94%, the selective rule reduced the accepted-sample error to 2.71% and 3.16% on Test1 and Test2 without benchmark-specific cutoff selection. These findings are interpreted as model-level evidence rather than causal biological mechanisms. Frozen-model analyses indicate that the conformer contribution is small and non-uniform: under the structural expert, substantial geometric variation does not necessarily translate into stable outcome-aligned probability variation.

Keywords: peptide toxicity prediction; multimodal deep learning; protein language model; bidirectional Mamba; pLDDT-aware multi-scale 3D modeling; interpretability

1 INTRODUCTION

Peptides are increasingly used as therapeutic candidates because of their high target specificity and functional diversity [1]. However, peptide toxicity remains a major safety concern during drug development, and the accurate and efficient identification of toxic peptides is a major bottleneck in peptide-based drug discovery [2]. Because conventional experimental toxicity assays are costly, time-consuming, and difficult to scale, reliable computational predictors are highly desirable.

Computational peptide toxicity prediction has evolved from traditional machine learning methods based on handcrafted physicochemical features toward deep learning approaches with stronger representation-learning capability. Current mainstream methods can be roughly grouped into two categories. The first category operates on sequence-level (one-dimensional,

1D) and/or atomic-level (two-dimensional, 2D) representations. For example, ToxMSRC combines continuous bag-of-words (CBOW) embeddings, multi-scale convolutional neural networks, and a bidirectional long short-term memory network with residual connections, achieving strong performance on the benchmark dataset [2]. ToxPLTC integrates pooled ProtT5 embeddings, borderline-SMOTE augmentation, and a text convolutional neural network [3]. ToxiPep fuses context-aware sequence representations with atomic-level graphs through a cross-attention mechanism [4]. HyPepTox-Fuse further combines embeddings from multiple protein language models with conventional descriptors [5]. Although these models achieve strong performance within their respective modalities, they largely neglect the three-dimensional (3D) conformations of peptides, which are closely related to toxicity; cross-dimensional information interaction and mutual validation remain limited, and their interpretability is mostly confined to the sequence level.

The second category attempts to exploit 3D structural information. PeptiTox uses ESM2 sequence embeddings together with ESMFold-predicted 3D structures and geometric graph neural networks [6]. StrucToxNet feeds ProtT5 sequence embeddings and ESMFold-predicted structures into an equivariant graph neural network (EGNN) and systematically analyzes structural quality [7]. These studies demonstrate the value of 3D conformations for toxicity prediction. However, such methods are constrained by the limited accuracy of current structure prediction models on short peptides and typically rely on a single predicted conformation; structural confidence, i.e., the predicted local distance difference test (pLDDT) score, is either discarded through hard filtering or ignored, and multi-conformer ensembles are not considered. Moreover, the fusion between the sequence and structure branches remains relatively shallow, and no systematic multi-dimensional fusion that combines a task-adaptive sequence model with confidence-aware multi-scale structure modeling has been established.

To address these limitations, we propose GHXTox, an interpretable hierarchical dual-level fusion framework for peptide toxicity prediction. A task-adaptive 1D sequence expert combines a ProtT5 protein language model, adapted by low-rank adaptation (LoRA), with a bidirectional Mamba state-space encoder and three-seed ensembling [8–10]. A sequence-enhanced 3D structural expert integrates sequence semantics with spatial structure through pLDDT-aware cross-attention, ESMFold-derived geometry, full-atom chemical sites, and confidence gating across multiple structural scales; PepFlow and AlphaFold2/ColabFold conformer ensembles informed only training-side analyses and controlled ablations, and the final predictor uses the single-structure ESMFold anchor [11–14]. The two expert probabilities are fused at the probability level with weights fixed on training out-of-fold (OOF) predictions; the 1D probabilities are first calibrated on the same OOF table, and no benchmark labels are used during this selection. Gated sequence–structure cross-attention inside the structural expert further informs the interaction design [15]. Ablation experiments show that the contribution of structural evidence is dataset- and metric-dependent: fusion improves several fixed-threshold and probability-quality measures on Test1 while maintaining broadly comparable performance on Test2. Post hoc analyses characterize residue-level sensitivity, confidence gating, chemical-site perturbations, and expert disagreement without assigning causal biological meaning to these signals. The framework is evaluated on the frozen historical benchmarks described in Section 2.1.

In summary, the main contributions of this work are threefold: (1) we propose GHXTox, an interpretable hierarchical dual-level fusion framework that explores the complementary joint use of one-dimensional sequence and three-dimensional conformational information, integrating a task-adaptive 1D protein language model with pLDDT-aware multi-scale 3D structure modeling and combining the two experts at the probability level (Sections 2.5 and 3.2); (2) the 3D branch designs a multi-scale structural information extraction strategy spanning from local residue functional groups to the whole peptide, and incorporates pLDDT confidence into structural feature processing through continuous down-weighting and dynamic gating; and (3) extensive experiments on the frozen historical benchmark test sets show that GHXTox improves several

fixed-threshold and probability-quality measures on Test1 while maintaining broadly comparable performance on Test2, while ablation, robustness, and interpretability analyses characterize the conditions under which sequence and structural evidence are complementary.

2 MATERIALS AND METHODS

2.1 Datasets

We evaluate GHXTox on the benchmark datasets constructed by CAPTP [16] and subsequently adopted by ToxMSRC [2]. Following the data construction protocol of ToxMSRC [2], toxic peptide sequences were merged from three databases, namely CSM-Toxin [17], ToxinPred2 [18], and ATSE [19], and sequences longer than 50 residues were removed. Non-toxic sequences were retrieved from UniProt [20] using the query "NOT KW-0800 AND NOT KW-0020 AND reviewed:true", and sequences containing non-standard amino acids or exceeding 50 residues were excluded. After combining the two groups and removing samples with conflicting labels, CD-HIT [21] was applied with a sequence-identity threshold of 0.9 to eliminate redundant sequences, yielding 2,138 toxic and 5,375 non-toxic peptides. Following the same partition as ToxMSRC [2], we used 85% of the data as the training set and the remaining 15% as the benchmark Test1 set, resulting in 1,818 toxic and 4,569 non-toxic training peptides and 320 toxic and 806 non-toxic Test1 peptides. An additional benchmark Test2 set, containing 46 toxic and 536 non-toxic peptides, is used for frozen historical evaluation. Both Test1 and Test2 had been observed during historical project development and are therefore treated as frozen historical benchmarks rather than newly blinded external validation sets; their labels were not used in the formal OOF calibration, fusion-weight selection, or threshold-freezing procedure. ToxinPred 3.0 [22] was consulted as an external method and data-source reference during project development, but its records were not added to the present training set or to the formal Test1/Test2 result tables. Table 1 summarizes the statistics of the datasets used in this study.

Table 1: Statistics of the datasets used in this study.

Dataset	Toxic	Non-toxic	Total	Use
Training (benchmark)	1,818	4,569	6,387	Model training
Test1 (benchmark)	320	806	1,126	Benchmark test
Test2	46	536	582	Benchmark test

2.2 Overview of the Model

GHXTox is a hierarchical dual-level fusion framework for peptide toxicity prediction: a task-adaptive one-dimensional (1D) sequence expert and a sequence-enhanced three-dimensional (3D) structural expert generate independent probabilities, interact internally at the feature level, and are combined at the probability level.

The 1D expert processes the peptide sequence with a LoRA-adapted ProtT5 encoder [8, 9] followed by a bidirectional Mamba state-space model [10], averages three seed models, and applies OOF-fitted Platt calibration to produce p_{1D} (Section 2.3). The 3D expert integrates sequence semantics, residue geometry, full-atom chemical sites, and pLDDT confidence at five scales, combines sequence and spatial states through pLDDT-aware cross-attention, and emits p_{SE3D} (Section 2.4).

The two probabilities are combined at the probability level; the fusion rule, the decision threshold, and the final output are described in Section 2.5.




Figure 1: Overall architecture of GHXTox. The framework combines a task-adaptive 1D sequence expert with a pLDDT-aware structural expert through probability-level fusion.

2.3 Task-Adaptive 1D Sequence Modeling

The 1D sequence expert learns toxicity-related contextual semantics directly from peptide sequences. Instead of reducing a frozen protein-language-model output to a fixed mean vector, GHXTox preserves the residue-level representations of ProtT5, adapts the pretrained encoder to the toxicity task through low-rank adaptation (LoRA), models residue dependencies with a bidirectional Mamba encoder, and aggregates the residue states by masked mean pooling before classification. Three full-data models with different random seeds are combined by equal-weight probability averaging followed by Platt calibration fitted exclusively on training out-of-fold (OOF) predictions.

Each residue is first written in the space-separated format expected by the ProtT5 tokenizer, and a binary residue-validity mask separates genuine residue positions from special and padding tokens; this mask is reused throughout the Mamba scans and in the final pooling. The tokenized sequence is processed by the ProtT5-XL-UniRef50 encoder [8] with LoRA, yielding residue-level representations that retain position-specific contextual semantics. To adapt this general-purpose encoder to the toxicity task, LoRA [9] is applied to all of its linear layers with rank $r = 8$, scaling $\alpha = 16$, and dropout 0.1: the pretrained weights stay frozen, and only the zero-initialized low-rank update ($\mathbf{W} = \mathbf{W}_0 + \frac{\alpha}{r}\mathbf{BA}$) and the downstream modules are trainable. The 1024-dimensional representations are then projected into the 192-dimensional Mamba hidden space through a layer-norm–GELU–dropout block.

Two bidirectional Mamba layers [10] are then stacked after the projection block to capture the sequential dependencies relevant to peptide toxicity. Each directional block follows the standard selective state-space formulation with input-dependent discretization and a 16-dimensional recurrent state; forward and backward scans are applied to the masked sequence, and their outputs are concatenated, fused by a linear layer, and added through a residual connection, so every residue is contextualized by both its N-terminal and C-terminal contexts. Padding positions are zeroed so that they cannot inject information into the recurrent states. The resulting residue states are aggregated by masked mean pooling over the valid positions, and a layer-normalized single-output linear head yields the uncalibrated toxicity probability. Because non-toxic peptides far outnumber toxic peptides in the training data, a positive-class-weighted binary cross-entropy loss is used instead of SMOTE or Borderline-SMOTE, with the positive-class weight $w_+ = N_-/N_+$ recomputed from each fold's training partition; this emphasizes the minority class without generating synthetic samples or leaking held-out information.

To reduce the variance of a single training run, three 1D models are trained under identical settings with random seeds 42, 123, and 2025, and the ensemble score is the equal-weight arithmetic average of the three full-data models; no seed is selected on test performance and no seed-specific weight is introduced. Although averaging reduces variance, neural-network probabilities may remain miscalibrated, so a monotonic two-parameter Platt calibrator [23] is fitted to the training OOF scores (generated with the fixed group-aware five-fold partition, Section 2.5) and applied to the three-seed average at inference. Because the calibration is monotonic, it preserves the sample ranking. Test1/Test2 labels are not used for member selection, calibration fitting, or threshold optimization. The calibrated probability $p_{1\mathrm{D}}$ is the sequence-expert output used in the top-level fusion (Section 2.5); no additional calibrator is fitted after fusion.

The complete 1D pipeline, from the peptide sequence to the calibrated probability, is summarized as follows:

$$\mathbf{H}^{\mathrm{PLM}} = \mathrm{ProtT5}_{\mathrm{LoRA}}(\mathcal{S}) \in \mathbb{R}^{L\times 1024}, \quad \mathbf{X}^{(0)} = \mathrm{Proj}\left[\mathbf{H}^{\mathrm{PLM}}\right] \in \mathbb{R}^{L\times 192}, \tag{1}$$

$$\mathbf{h}_{1D} = \frac{\sum_{i=1}^{L} m_i \ \mathrm{BiMamba}\left(\mathbf{X}^{(0)}\right)_i}{\sum_{i=1}^{L} m_i} \in \mathbb{R}^{192}, \tag{2}$$

$$z_{1D} = \mathbf{w}_c^{\top}\,\mathrm{LN}\left(\mathbf{h}_{1D}\right) + b_c, \qquad p_{1D}^{\mathrm{raw}} = \sigma\left(z_{1D}\right), \tag{3}$$

$$p_{1D} = \sigma\left(a\ \mathrm{logit}\left(\mathrm{clip}\left(\frac{1}{3}\sum_{k=1}^{3} p^{(k)},\ \varepsilon,\ 1-\varepsilon\right)\right) + b\right) \tag{4}$$

where Proj is the layer-norm–GELU–dropout projection, $\mathbf{m}$ is the residue-validity mask, $p^{(k)}$ is the probability of the k-th seed model, and a, b are the OOF-fitted monotonic Platt parameters (with logit clip $\varepsilon = 10^{-6}$).

2.4 pLDDT-Aware Multi-Scale 3D Structural Modeling

Peptide toxicity is influenced not only by amino acid composition and linear residue order but also by the three-dimensional (3D) arrangement of charged groups, hydrophobic regions, aromatic systems, and sulfur-containing moieties. Because peptides are generally short, conformationally flexible, and poorly covered by experimentally determined structures, treating a single predicted conformation as an error-free structural observation may amplify structure-prediction errors, whereas Cα-only or peptide-level summary representations fail to capture the local spatial-chemical environments that are relevant to toxicity.

To address these limitations, GHXTox employs a pLDDT-aware multi-scale structural expert that captures complementary information at five levels: residue semantics, spatial residue neighborhoods, full-atom chemical sites, peptide-level global properties, and conformer-ensemble statistics (Figure 2). Sections 2.4.1–2.4.6 describe, in turn, single-structure prediction and conformer preparation, residue feature construction and the hybrid geometric graph, pLDDT-aware equivariant graph encoding, full-atom chemical-site message passing with the availability-masked conformer-ensemble logit residual, sequence–structure cross-attention, and global feature integration with classification. Throughout, pLDDT is treated as a continuous reliability signal rather than a hard filter: low-confidence structural evidence is down-weighted in geometric edge weighting, chemical-site messages, and residue- and peptide-level structural gating instead of being removed, preserving structural coverage while limiting the influence of uncertain coordinates. pLDDT is interpreted here as a local confidence estimate produced by the structure-prediction model, not as an experimentally determined measure of structural accuracy, conformational flexibility, or biological activity.

Figure 2: Detailed architecture of the sequence-enhanced structural expert. The structural expert integrates ESM2-enhanced residue semantics, a pLDDT-aware geometric residue graph, full-atom chemical-site message passing, and availability-masked conformer-ensemble statistics. Residue-level structural states are continuously modulated by node-level confidence before serving as keys and values in sequence–structure cross-attention. A peptide-level confidence gate further controls the fused structural context, while conformer statistics provide a zero-initialized logit residual only when valid ensemble information is available.

2.4.1 Peptide Structure Prediction and Conformer Preparation

For a peptide sequence of length L, $S = (a_1, a_2, \ldots, a_L)$, ESMFold is first used to predict its three-dimensional structure [11]. The predicted structure is stored as a full-atom PDB file, from which residue-level Cα coordinates, backbone coordinates, full-atom-derived chemical-site coordinates, and pLDDT scores are extracted. The Cα coordinates are collected as $\mathbf{X} = [\mathbf{x}_1, \ldots, \mathbf{x}_L]^\top \in \mathbb{R}^{L\times 3}$, $\mathcal{A}$ denotes the full-atom-PDB-derived backbone and chemical-site geometry, and $\mathbf{q} = (q_1, \ldots, q_L) \in [0,1]^L$ contains the residue-level pLDDT confidence scores rescaled to $[0,1]$, where q_i denotes the residue-level pLDDT score of residue i. The Cα coordinates serve as the primary spatial variables of the residue-level equivariant graph, whereas the full-atom coordinates are used to construct local chemical sites. Before geometric encoding, the coordinates are centered at the peptide centroid to remove the effect of absolute translation.

A single predicted structure provides a common structural anchor but cannot represent potential conformational heterogeneity. The conformer-residual stage was therefore trained on a multi-source conformer variant using a 2,795-peptide cohort with up to eight validated, aligned conformers per peptide. PepFlow is a generalized Boltzmann generator that performs direct all-atom conformational-ensemble sampling from the peptide energy landscape rather than predicting a single structure; it samples eight conformations per input peptide during training and has been shown to efficiently recapitulate experimental ensembles of short linear motifs (SLiMs, typically 3–15 residues) and to generate all-atom conformations for peptides of different lengths [14]. Short-peptide conformations are therefore provided by PepFlow, which is applied to peptides of at most 15 residues (the actual training cohort spans 11–15 residues and comprises 761 records with eight conformers each). Longer peptides are provided by AlphaFold2/ColabFold: AlphaFold2 is a high-accuracy single-structure predictor [12], and its peptide-structure performance has been systematically evaluated for peptides of 16–60 residues [24], an interval that covers the 16–30-residue cohort; ColabFold, an MSA-accelerated AlphaFold2 implementation [13], generates candidate conformations from five models and multiple seeds, which are filtered by an average-pLDDT quality floor and then reduced to eight diverse conformers per peptide by farthest-point sampling on Kabsch-aligned Cα-RMSD, yielding 2,034 training records. These sources are represented explicitly in the residual head; nevertheless, generator identity remains partially coupled to peptide length and is treated as a limitation rather than as an independently identified causal factor.

For controlled ablation only, a test-side conformer cache was constructed with fixed source and sequence-matching policies without using Test1 or Test2 labels; these caches are not used by the final benchmark predictor or the public inference interface. To remove arbitrary rigid-body differences and make the statistics comparable across peptides, every admitted ensemble is normalized before being consumed by the residual branch. An ensemble is represented as $\mathcal{C} = \{\mathbf{X}^{(1)}, \ldots, \mathbf{X}^{(M)}\}$, $1 \le M \le 8$, where $\mathbf{X}^{(m)} \in \mathbb{R}^{L\times 3}$ denotes the Cα coordinates of conformer m. First, each conformer must reproduce the input FASTA sequence residue by residue (both the Cα sequence and the chemical-site parse are verified); non-matching conformers are rejected, so all conformers share the same residue-index order without reordering or truncation. Second, taking the first conformer as the reference, every conformer is centered and aligned to the reference frame by Kabsch alignment, which obtains an optimal rotation by singular value

decomposition with reflection correction, yielding the aligned coordinates and the per-residue fluctuation:

$$\tilde{\mathbf{X}}^{(m)} = \left(\mathbf{X}^{(m)} - \mathbf{1}_L \bar{\mathbf{x}}^{(m)\top}\right) \mathbf{R}_m, \qquad \mathbf{R}_m = \mathbf{U}_m \mathbf{V}_m^\top,$$
$$\mathrm{RMSF}_i = \left[\frac{1}{M} \sum_{m=1}^{M} \left\| \tilde{\mathbf{x}}_i^{(m)} - \bar{\mathbf{x}}_i \right\|_2^2\right]^{1/2}, \tag{5}$$

where $\tilde{\mathbf{X}}^{(m)}$ denotes the aligned Cα coordinates of conformer m, $\mathbf{1}_L$ is the all-ones vector, $\bar{\mathbf{x}}^{(m)}$ is the centroid of conformer m, $\mathbf{R}_m$ is the optimal rotation obtained from the singular value decomposition of the centered cross-covariance between conformer m and the reference conformer (with reflection correction), $\bar{\mathbf{x}}_i$ is the ensemble-mean coordinate of residue i, and RMSF_i is the corresponding per-residue root-mean-square fluctuation.

After alignment, the ensemble-mean coordinates, per-residue root-mean-square fluctuation (RMSF), and per-conformer RMSD are computed, whereas the rotation/translation-invariant quantities – per-conformer radius of gyration, per-residue-pair distance mean and standard deviation, and 6/8/10 Å contact occupancies (the fraction of conformers in which a residue pair is closer than the cutoff) – are computed directly from the raw coordinates. The resulting statistics are rescaled by fixed factors (e.g., RMSF/10 and distances/20) into bounded residue-level (8-dimensional) and peptide-level (12-dimensional) features, and the conformer count is normalized as $M/8$. Regarding confidence, AlphaFold2/ColabFold conformers carry the real pLDDT read from the PDB B-factor column, whereas PepFlow does not output pLDDT and is assigned a fixed substitute value of 0.7; this substitute is explicitly not treated as pLDDT in the single-structure quality gating, which remains governed by the ESMFold backbone, and PepFlow contributes only cross-conformer fluctuation and occupancy information. The normalized ensemble statistics are consumed by a small logit residual branch controlled by a binary availability indicator c_{conf} (mechanism detailed in Section 2.4.4); when $c_{\mathrm{conf}} = 0$, the correction vanishes exactly and the model reduces to the single-structure pathway. Missing conformer statistics are treated as unavailable data rather than as evidence of structural rigidity; the model draws no flexibility inference from the absence of conformers and simply falls back to the single-structure prediction.

The generated conformers are computational samples rather than experimentally determined trajectories or rigorous thermodynamic ensembles. Consequently, RMSF, contact occupancy, and distance variance are interpreted as sampling-derived descriptors of conformational variation rather than direct measurements of peptide dynamics in solution.

2.4.2 Residue Feature Construction and Hybrid Geometric Graph

Given the predicted single structure and its confidence scores (Section 2.4.1), the structural expert constructs two complementary residue-level representations: an internal sequence-semantic representation and a spatial-geometric representation. The sequence-semantic subbranch uses frozen ESM2 residue embeddings [11] and a lightweight Transformer; unlike the independent top-level 1D prediction expert of Section 2.3, it serves the residue-level sequence–structure alignment inside the structural expert.

For residue i, the input to the internal sequence-semantic subbranch is

$$\mathbf{u}_i^{\mathrm{seq}} = \left[\mathbf{e}_i^{\mathrm{AA}} \parallel \mathbf{e}_i^{\mathrm{group}} \parallel \mathbf{f}_i^{\mathrm{res}} \parallel P_{\mathrm{ESM}}\left(\mathbf{e}_i^{\mathrm{ESM2}}\right)\right], \tag{6}$$

where $\mathbf{e}_i^{\mathrm{AA}} \in \mathbb{R}^{32}$ is the amino acid category embedding, $\mathbf{e}_i^{\mathrm{group}} \in \mathbb{R}^{12}$ is the functional-group category embedding, $\mathbf{f}_i^{\mathrm{res}} \in \mathbb{R}^{42}$ denotes the explicit residue-level physicochemical descriptors, and $\mathbf{e}_i^{\mathrm{ESM2}} \in \mathbb{R}^{1280}$ is the ESM2-650M residue representation; the projection P_{ESM} maps the ESM2 representation to 128 dimensions. Stacking the residue-level feature vectors yields the sequence-feature matrix $U_{\mathrm{seq}} \in \mathbb{R}^{L \times 214}$ ($214 = 32 + 12 + 42 + 128$). After a linear projection and positional encoding, a two-layer Transformer encoder (hidden size 128, four attention heads,

feed-forward dimension 512) produces the contextualized sequence states $\mathbf{H}^{\mathrm{seq}} \in \mathbb{R}^{L\times 128}$, which encode the contextual sequence semantics of each residue and serve as the query representation in the sequence–structure cross-attention module.

In the spatial subbranch, the initial representation of residue i is

$$\mathbf{h}_i^{(0)} = P_{\mathrm{sp}}\left[\mathbf{f}_i^{\mathrm{res}} \parallel \mathbf{g}_i^{\mathrm{geo}} \parallel q_i \parallel P_{\mathrm{ESM}}\left(\mathbf{e}_i^{\mathrm{ESM2}}\right)\right], \tag{7}$$

where $\mathbf{g}_i^{\mathrm{geo}} \in \mathbb{R}^{16}$ is a lightweight geometric descriptor derived from the Cα coordinates and pLDDT scores, including (i) residue-level pLDDT and local confidence statistics; (ii) radial position, contact fractions, and soft spatial density; (iii) nearest-neighbor, nonlocal-neighbor, and local sequential distances; and (iv) sine/cosine encodings of the Cα-trace angles and torsions. The residue-level confidence q_i additionally enters the initial representation as an explicit scalar. These deterministic descriptors provide stable local geometric priors without imposing an overly complex handcrafted representation for short and uncertain predicted peptide structures.

GHXTox then constructs a hybrid residue graph $\mathcal{G} = (\mathcal{V}, \mathcal{E}_{\mathrm{seq}} \cup \mathcal{E}_{\mathrm{knn}})$ in which each residue corresponds to one node: sequential edges $\mathcal{E}_{\mathrm{seq}}$ connect adjacent residues and preserve peptide-chain continuity, whereas $\mathcal{E}_{\mathrm{knn}}$ connects each residue to its 10 nearest spatial neighbors and is symmetrized. The hybrid graph therefore captures both covalent sequence order and nonlocal spatial contacts while avoiding large variations in graph density that may arise from a single fixed-distance cutoff; equivalently, $A_{ij} \in \{0, 1\}$ indicates whether residues i and j are connected by a sequential or k-nearest-neighbor edge.

For residues i and j, the Cα distance $d_{ij} = \|\mathbf{x}_i - \mathbf{x}_j\|_2$ is encoded by 16 radial basis functions with centers μ_k uniformly spaced over 0–24 Å, $\phi_k(d_{ij}) = \exp[-\gamma(d_{ij} - \mu_k)^2]$ with $\gamma = 1/(\mu_{k+1} - \mu_k)^2$. The base edge representation additionally includes the pairwise structural confidence and the normalized sequence separation:

$$c_{ij} = \sqrt{q_i q_j}, \qquad s_{ij} = \frac{\log(1 + |i - j|)}{\log(L + 1)}, \tag{8}$$

so that s_{ij} is small for sequentially adjacent residues and approaches one for distant residues. The resulting edge feature is therefore $\mathbf{e}_{ij} = [\boldsymbol{\phi}(d_{ij}) \parallel c_{ij} \parallel s_{ij}]$, which lets the model distinguish sequentially adjacent contacts, long-range spatial contacts, and contacts supported by different levels of structural confidence.

2.4.3 pLDDT-Aware Equivariant Graph Encoding

To learn three-dimensional representations without relying on a particular global coordinate frame, the spatial branch employs three E(3)-equivariant graph neural network layers [25]. The network updates residue features using rotation- and translation-invariant quantities while updating coordinates equivariantly. Consequently, a global rigid transformation of the peptide structure does not change the predicted toxicity, whereas intermediate coordinate representations transform consistently with the input.

At layer ℓ, the message from residue j to residue i is computed as $\mathbf{m}_{ij}^{(\ell)} = \phi_e^{(\ell)}[\mathbf{h}_i^{(\ell)} \parallel \mathbf{h}_j^{(\ell)} \parallel \mathbf{e}_{ij}^{(\ell)}]$, where $\phi_e^{(\ell)}$ is a message multilayer perceptron. To prevent uncertain or distant contacts from contributing as strongly as local high-confidence contacts, a continuous edge weight is defined as

$$w_{ij}^{(\ell)} = A_{ij}\, \exp\left(-\frac{d_{ij}^{(\ell)}}{12}\right)\left[q_{\min} + (1 - q_{\min})\, c_{ij}^{\rho}\right], \qquad q_{\min} = 0.1, \quad \rho = 1.5, \tag{9}$$

The term $\exp(-d_{ij}^{(\ell)}/12)$ imposes a smooth distance decay with a characteristic decay length of 12 Å, and both the distance and the edge weight are recomputed at each layer from the

current coordinates. Here, $A_{ij} \in \{0,1\}$ is the adjacency indicator of the hybrid graph defined in Section 2.4.2, and $c_{ij} = \sqrt{q_i q_j}$ is the pairwise structural confidence derived from the residue-level pLDDT scores q_i and q_j defined in Section 2.4.1. The minimum weight $q_{\min}$ prevents low-confidence regions from being completely disconnected, whereas the exponent ρ increases the relative contribution of high-confidence contacts. The distance-decay term further reduces the influence of more distant spatial neighbors.

These pLDDT-aware weighted edge messages are then aggregated at each node with a normalization floor. For node i, the aggregated message is $\mathbf{m}_i^{(\ell)} = \sum_j w_{ij}^{(\ell)} \mathbf{m}_{ij}^{(\ell)} / \max(\sum_j w_{ij}^{(\ell)}, 1)$, the node features are updated as $\mathbf{h}_i^{(\ell+1)} = \mathrm{LN}\{\mathbf{h}_i^{(\ell)} + \phi_h^{(\ell)}[\mathbf{h}_i^{(\ell)} \parallel \mathbf{m}_i^{(\ell)}]\}$, and the coordinates are updated equivariantly as $\mathbf{x}_i^{(\ell+1)} = \mathbf{x}_i^{(\ell)} + 0.05 \sum_j \alpha_{ij}^{(\ell)} (\mathbf{x}_i^{(\ell)} - \mathbf{x}_j^{(\ell)}) / \max(\sum_j w_{ij}^{(\ell)}, 1)$, where $\alpha_{ij}^{(\ell)} = \tanh[\phi_x^{(\ell)}(\mathbf{m}_{ij}^{(\ell)})]\, w_{ij}^{(\ell)}$ is a bounded coordinate-update coefficient generated from the edge message and pairwise distances. The coordinates are recentered after every layer to reduce numerical drift. Because the update depends only on scalar messages, distances, and relative coordinate vectors, the operation remains equivariant to rigid rotations and translations.

Each layer update performs one round of message passing, i.e., one hop of spatial-context propagation over the hybrid graph, so a single layer can aggregate only the direct neighborhood of each node. Because toxicity-related spatial patterns often span multiple residues (for example, spatial clusters formed by several charged, aromatic, or hydrophobic residues), the model must aggregate multi-hop neighborhood information along the graph; stacking layers therefore enlarges the receptive field hop by hop: the first layer primarily encodes direct geometric neighbors, whereas subsequent layers integrate higher-order spatial environments through repeated message passing. GHXTox uses three layers, a depth that balances context integration against model complexity and overfitting risk on short and uncertain predicted peptide structures. Unlike approaches that simply append pLDDT as an ordinary node feature, GHXTox uses pLDDT to directly modulate the strength of geometric messages, allowing structural uncertainty to influence representation learning at the propagation stage. Low pLDDT does not imply that a residue is biologically unimportant; it may reflect prediction error or genuine conformational flexibility, so the model reduces the reliability of uncertain coordinate evidence while preserving the residue's sequence-semantic and physicochemical features.

2.4.4 Full-Atom Chemical-Site Message Passing

A Cα-based residue graph captures the global fold and spatial neighborhoods but cannot resolve chemically distinct moieties within the same side chain. For example, tyrosine contains both an aromatic ring and a hydroxyl group, whereas tryptophan contains an aromatic system and an indole nitrogen. Compressing each side chain into a single centroid would mix these chemically different moieties. GHXTox therefore extracts chemistry-aware pseudo-sites from the predicted full-atom PDB structure and processes them with a dedicated local chemical branch.

To retain this chemical detail, up to two chemical sites are kept for each residue. Site identity is represented by an eight-dimensional multi-hot vector $\mathbf{t}_{ir} \in \{0,1\}^8$ allowing overlapping types: positive, negative, donor, acceptor, aromatic, hydrophobic, sulfur, and conformational, where r indexes the chemical site within residue i. Multiple types may be assigned to the same site: for example, the cysteine sulfur site is labeled as donor, hydrophobic, and sulfur-containing, whereas the proline ring is labeled as hydrophobic and conformationally constrained; the aromatic ring and hydroxyl group of tyrosine are represented as separate sites, as are the aromatic system and the indole NE1 nitrogen (donor) of tryptophan.

Each site is further localized and oriented in the predicted structure: its coordinate is the mean position of the heavy atoms defining the corresponding chemical moiety, and its orientation is represented by either a bond direction or an unsigned plane normal. Because the sign of a plane normal is arbitrary, downstream directional features use absolute cosines, preserving rotation

invariance and eliminating orientation-sign ambiguity. Combining these attributes, the initial representation of site r in residue i is $\mathbf{z}_{ir}^{(0)} = \phi_{\text{site}}[\mathbf{t}_{ir} \parallel q_i \parallel o_{ir}^{\text{valid}}]$, where q_i is the pLDDT score of the parent residue and o_{ir}^{valid} indicates whether a reliable orientation could be constructed; the input is projected into a 64-dimensional hidden space.

Because chemical interactions depend on spatial proximity, edges are established between valid sites separated by no more than 16 Å; same-residue site edges are kept, preserving spatial relationships between chemically different moieties in complex side chains. Each edge carries four complementary feature families. First, the raw distance in Å is encoded using 16 radial basis functions, $\boldsymbol{\phi}_{\text{raw}}(d_{uv}) \in \mathbb{R}^{16}$. Second, a peptide-size-normalized distance is constructed. The radius of gyration of the Cα coordinates is

$$R_g = \sqrt{\frac{1}{L}\sum_{i=1}^{L} \|\mathbf{x}_i - \bar{\mathbf{x}}\|_2^2}, \qquad \bar{\mathbf{x}} = \frac{1}{L}\sum_{i=1}^{L} \mathbf{x}_i, \qquad \bar{d}_{uv} = \frac{d_{uv}}{R_g}, \tag{10}$$

where $\bar{\mathbf{x}}$ denotes the centroid of the valid Cα coordinates, and the normalized distance is encoded by eight radial basis functions over the interval 0–4, $\boldsymbol{\phi}_{\text{norm}}(\bar{d}_{uv}) \in \mathbb{R}^8$. The raw representation describes the physical separation in Å, whereas the normalized representation describes the separation relative to the overall peptide size, allowing the model to distinguish, for example, an 8 Å contact in a compact short peptide from an 8 Å contact in a larger peptide. Third, four rotation-invariant orientation features are used, $\mathbf{o}_{uv} = [|\mathbf{o}_u \cdot \mathbf{r}_{uv}|, |\mathbf{o}_v \cdot \mathbf{r}_{vu}|, |\mathbf{o}_u \cdot \mathbf{o}_v|, o_{uv}^{\text{valid}}]$, which describe the alignment of the source orientation with the intersite direction, the alignment of the target orientation with the reverse direction, the mutual orientation of the two sites, and orientation availability. Fourth, six explicit compatibility channels are used: opposite-charge, donor–acceptor, aromatic–aromatic, positive–aromatic (cation–π), sulfur–sulfur, and hydrophobic–hydrophobic compatibility. These channels encode candidate chemical compatibility patterns available to the model; they do not imply that a true salt bridge, hydrogen bond, cation–π interaction, disulfide bond, or hydrophobic core is present in the predicted structure.

Combining these families yields the full chemical-site edge representation

$$\mathbf{e}_{uv}^{\text{chem}} = \left[\boldsymbol{\phi}_{\text{raw}}(d_{uv}) \parallel \boldsymbol{\phi}_{\text{norm}}(\bar{d}_{uv}) \parallel \mathbf{o}_{uv} \parallel \mathbf{c}_{uv}^{\text{chem}} \parallel \sqrt{q_u q_v}\right], \tag{11}$$

in which pLDDT enters the chemical-site features as a confidence channel. At layer l, each site message is computed from the two site states and the edge representation, weighted by the pairwise confidence, and aggregated over the neighborhood. After two message-passing layers, valid sites belonging to the same residue are mean-pooled, and the residue-level chemical residual and the chemical-enhanced spatial state are

$$\begin{aligned}
\mathbf{m}_{uv}^{(l)} &= \phi_{\text{chem}}^{(l)}\left[\mathbf{z}_u^{(l)} \parallel \mathbf{z}_v^{(l)} \parallel \mathbf{e}_{uv}^{\text{chem}}\right], \\
\bar{\mathbf{m}}_v^{(l)} &= \frac{\sum_{u\in\mathcal{N}(v)} \sqrt{q_u q_v}\, \mathbf{m}_{uv}^{(l)}}{\max\left(\sum_{u\in\mathcal{N}(v)} \sqrt{q_u q_v},\, 1\right)}, \\
\Delta\mathbf{h}_i^{\text{chem}} &= \mathbf{W}_{\text{chem}} \operatorname*{Mean}_{r\in\mathcal{S}_i}\left(\mathbf{z}_{ir}^{(2)}\right), \\
\mathbf{h}_i^{\text{sp}} &= \mathbf{h}_i^{\text{EGNN}} + \Delta\mathbf{h}_i^{\text{chem}},
\end{aligned} \tag{12}$$

where the aggregation weights the incoming messages by the pairwise confidence $\sqrt{q_u q_v}$, continuing the pLDDT-aware weighting of information extraction. The projection $\mathbf{W}_{\text{chem}}$ and its bias $\mathbf{b}_{\text{chem}}$ are zero-initialized, so that $\Delta\mathbf{h}_i^{\text{chem}} = 0$ at the beginning of training. This conservative residual design allows the new chemical-site branch to progressively learn useful corrections from an intact geometric backbone rather than perturbing the existing spatial representation with a randomly initialized contribution.

Beyond these residue-level corrections, the structural expert additionally allows multi-conformer statistics to refine the prediction through a logit-level residual [26]. To avoid the

high cost of running the complete geometric network independently on every conformer, GHX-Tox compresses the ensemble descriptors normalized in Section 2.4.1 into a lightweight statistical residual: residue-level ensemble features are encoded and pooled with both masked-mean and masked-max operations, the peptide-level descriptor is processed by a separate encoder, and the generator identity (PepFlow, AlphaFold2/ColabFold, or another admitted generator) is encoded by a three-dimensional one-hot vector whose learned source embedding is concatenated with the base structural embedding and the two ensemble embeddings to produce a raw logit residual through a small network with a zero-initialized final layer. The effective residual is the product of the availability indicator and a learned weight (initialized to 0.25 and regularized by an L1 penalty); when the availability indicator is zero, the residual is exactly zero and the model falls back to the single-structure prediction. The inference protocol is described in Section 2.5, and the ablation analysis in Section 3.3.

2.4.5 pLDDT-Aware Sequence–Structure Cross-Attention

After the EGNN and the chemical-site residual are applied, the model obtains the chemical-enhanced spatial representation $\mathbf{H}^{\mathrm{sp}} = [\mathbf{h}_1^{\mathrm{sp}}, \ldots, \mathbf{h}_L^{\mathrm{sp}}]^\top \in \mathbb{R}^{L\times 128}$, where $\mathbf{h}_i^{\mathrm{sp}}$ is defined in Eq. (12). Spatial information alone does not determine whether a structural pattern is relevant to the current sequence context: similar hydrophobic contacts may have different implications depending on residue identities and sequence positions. GHXTox therefore uses pLDDT-aware cross-attention within the structural expert, allowing contextualized sequence states to selectively retrieve spatial evidence.

A node-level gate is first constructed for each residue from the 42-dimensional residue descriptors and the pLDDT score:

$$\begin{aligned} g_i^{\mathrm{base}} &= \phi_{\mathrm{node}}\left[\mathbf{f}_i^{\mathrm{res}} \parallel q_i\right], \\ \mathbf{c}_i^{\mathrm{node}} &= \left[\frac{q_i-\mu_q}{T_q},\ \frac{(q_i-\mu_q)^2}{T_q^2},\ \mathbb{I}(q_i<0.55)\right], \\ r_i^{\mathrm{node}} &= 0.5 + \sigma\left(\mathbf{w}_n^\top \mathbf{c}_i^{\mathrm{node}} + b_n\right), \\ g_i^{\mathrm{node}} &= \mathrm{clamp}\left(g_i^{\mathrm{base}}\, r_i^{\mathrm{node}},\ 0, 1\right), \end{aligned} \tag{13}$$

where $\mu_q = 0.70$, $T_q = 0.12$, and the residual confidence vector $\mathbf{c}_i^{\mathrm{node}}$ allows the gate to adapt to the local confidence distribution. The spatial representation is then continuously down-weighted as $\widehat{\mathbf{H}}^{\mathrm{sp}} = \mathbf{H}^{\mathrm{sp}} \odot \mathbf{g}^{\mathrm{node}}$, with the node-level gate vector $\mathbf{g}^{\mathrm{node}} \in [0,1]^L$ broadcast across the feature dimension.

In the cross-attention operation, the contextualized sequence representation serves as the query, and the gated spatial representation serves as the key and value [27]:

$$\mathbf{H}^{\mathrm{cross}} = \mathrm{MHA}\left(Q = \mathbf{H}^{\mathrm{seq}}, K = \widehat{\mathbf{H}}^{\mathrm{sp}}, V = \widehat{\mathbf{H}}^{\mathrm{sp}}\right). \tag{14}$$

This direction has a direct interpretation: each residue position retrieves spatial evidence according to its contextual sequence representation. The operation is not a direct feature interaction between the LoRA-ProtT5–Mamba expert and the structural expert; it occurs internally between the ESM2-enhanced sequence states and the geometric states of the structural expert.

In addition to residue-level gating, a peptide-level gate is generated from the overall structure-confidence profile. The model first summarizes the profile by the mean pLDDT $\bar{q}$, the minimum pLDDT $q_{\min}$, and the low-confidence fraction $r_{\mathrm{low}} = \frac{1}{L}\sum_{i=1}^{L}\mathbb{I}(q_i < 0.55)$, and constructs the peptide-level confidence vector $\mathbf{c}^{\mathrm{pep}} = [(\bar{q}-\mu_q)/T_q,\ (q_{\min}-\mu_q)/T_q,\ r_{\mathrm{low}}]$. The

base peptide-level gate and its residual-adjusted form are

$$
\begin{aligned}
g_{\text{pep}}^{\text{base}} &= \phi_{\text{global}}\left[\bar{q},\ q_{\min},\ r_{\text{low}}\right], \\
r_{\text{pep}} &= 0.5 + \sigma\left(\mathbf{w}_{\text{pep}}^{\top}\mathbf{c}^{\text{pep}} + b_{\text{pep}}\right), \\
g_{\text{pep}} &= \text{clamp}\left(g_{\text{pep}}^{\text{base}}\, r_{\text{pep}},\ 0, 1\right),
\end{aligned}
\tag{15}
$$

where the peptide-level residual scale is analogous to, but separately parameterized from, the node-level residual scale, and $g_{\text{pep}} \in [0, 1]$ denotes the scalar peptide-level structural gate.

The final residue-level fusion representation combines the sequence state with the gated structural context, $\mathbf{H}^{\text{fused}} = \text{LN}\left[\mathbf{H}^{\text{seq}} \parallel g_{\text{pep}}\, \mathbf{H}^{\text{cross}}\right]$. The two gating levels answer complementary questions: how reliable the structural evidence is at an individual residue position, and how strongly the structural branch should be trusted for the peptide as a whole. The sequence representation is always kept, whereas the structural context is dynamically scaled according to prediction confidence. Consequently, when the predicted structure has low overall confidence, the structural expert can still rely on its internal sequence-semantic pathway without allowing uncertain coordinates to dominate the classification.

2.4.6 Global Feature Integration and Structural Classification

After pLDDT-aware cross-attention, each valid residue is represented by a 256-dimensional fused vector obtained by concatenating the 128-dimensional internal sequence state with the 128-dimensional structural context. Masked mean pooling is applied over the valid residue positions, and the pooled vector is concatenated with five global physicochemical descriptors before a three-layer MLP produces the base structural logit; the availability-masked conformer correction described in Section 2.4.4 is then added, and a sigmoid yields the final structural-expert probability

$$
p_{\text{SE3D}} = \sigma\left(\phi_{\text{cls}}\left[\left(\frac{\sum_{i=1}^{L} m_i\, \mathbf{H}_i^{\text{fused}}}{\sum_{i=1}^{L} m_i}\right) \parallel \mathbf{f}_{\text{pep}}^{\text{phys}}\right] + c_{\text{conf}}\, \lambda_{\text{conf}}\, \Delta z_{\text{conf}}^{\text{raw}}\right),
\tag{16}
$$

where the mask excludes padding positions from the pooled representation; $\mathbf{f}_{\text{pep}}^{\text{phys}} \in \mathbb{R}^5$ contains the normalized peptide length, the length-normalized net charge, the aromatic-residue fraction, the cysteine fraction, and the scaled mean hydropathy; ϕ_{cls} is a three-layer MLP with dimensions $261 \to 128 \to 64 \to 1$, each hidden layer applying GELU activation and dropout; and the conformer-correction term is nonzero only when valid ensemble information is available (Section 2.4.4), so under the benchmark and public inference protocol $c_{\text{conf}} = 0$ and p_{SE3D} reduces to $\sigma(z_{\text{base}})$, i.e., the single-structure base logits. Unlike maximum pooling, masked mean pooling integrates structural evidence distributed across residue positions, which is appropriate when toxicity-related spatial patterns are not confined to a single local region. The resulting probability is passed directly to the dual-expert fusion in Section 2.5; the standalone structural threshold is used only for branch-specific analyses.

2.5 Fusion and Final Output

The 1D expert emits the OOF-calibrated probability p_{1D} (Section 2.3), and the structural expert emits p_{SE3D} (Section 2.4). The two probabilities are fused linearly in probability space with weights frozen on training out-of-fold (OOF) predictions:

$$
p_{\text{GHXTox}} = 0.72\, p_{\text{1D}} + 0.28\, p_{\text{SE3D}},
\tag{17}
$$

The fused probability p_{GHXTox} is the model's continuous toxicity-probability output; it is binarized directly at the OOF-frozen threshold, predicting toxic ($\hat{y} = 1$) if $p_{\text{GHXTox}} \geq$

0.47022256531284556 and non-toxic ($\hat{y} = 0$) otherwise. The default output is therefore $(p_{\mathrm{GHXTox}}, \hat{y})$. Experiments showed that directly emitting the fused probability yields the best overall performance, so no additional network or calibration is applied after fusion.

The two experts were trained independently because they differ in input representation, parameter scale, and optimization behavior (the 1D and 3D loss, calibration, and training details are described in Sections 2.3 and 2.4). Group-aware training OOF predictions were used for calibration, fusion-weight selection, and threshold determination, and Test1/Test2 labels were excluded from all of these procedures. The training sequences were clustered by CD-HIT at a sequence-identity threshold of 0.80, with all peptides in the same homology group confined to the same fold; each fold was predicted by a model trained only on its complement, giving every training peptide a single OOF probability independent of its own optimization. Both experts were optimized with AdamW [28]. The fusion weight and decision threshold were selected by maximizing MCC on the complete training OOF table (with BACC as the secondary tie-break criterion and a leave-one-fold-out check), yielding $w_{\mathrm{1D}} = 0.72$, $w_{\mathrm{SE3D}} = 0.28$, and $\tau = 0.47022256531284556$; these values were then frozen and applied unchanged to Test1 and Test2. In the final benchmark and public inference protocol, the conformer availability mask is fixed to zero and the structural probability is read from the single-structure base logits.

2.6 Evaluation Criteria

Given the class-imbalanced benchmarks (Test2 has 46 toxic and 536 non-toxic peptides), MCC and BACC served as the primary threshold-dependent metrics, with ACC, sensitivity (SN), specificity (SP), precision, and F1 reported for completeness; AUROC/AUPRC quantified ranking performance, and Brier/ECE-10 assessed probability quality. Threshold-dependent metrics used the fixed OOF-derived threshold (Section 2.5); ranking and calibration metrics used the continuous probabilities. Binary predictions $\hat{y}_i = \mathbb{I}[p_i \geq \tau]$ were summarized by $\mathrm{ACC} = (\mathrm{TP}+\mathrm{TN})/N$, $\mathrm{SN} = \mathrm{TP}/(\mathrm{TP}+\mathrm{FN})$, $\mathrm{SP} = \mathrm{TN}/(\mathrm{TN}+\mathrm{FP})$, $F_1 = 2\mathrm{TP}/(2\mathrm{TP}+\mathrm{FP}+\mathrm{FN})$, and $\mathrm{BACC} = (\mathrm{SN}+\mathrm{SP})/2$. MCC [29], Brier [30], and ten-bin ECE-10 (final bin includes $p_i = 1$) are

$$\begin{aligned} \mathrm{MCC} &= \frac{\mathrm{TP}\,\mathrm{TN} - \mathrm{FP}\,\mathrm{FN}}{\sqrt{(\mathrm{TP}+\mathrm{FP})(\mathrm{TP}+\mathrm{FN})(\mathrm{TN}+\mathrm{FP})(\mathrm{TN}+\mathrm{FN})}}, \\ \mathrm{Brier} &= \frac{1}{N}\sum_{i=1}^{N}(p_i - y_i)^2, \\ \mathrm{ECE}_{10} &= \sum_{m=1}^{10}\frac{|\mathcal{B}_m|}{N}\,\left|\mathrm{conf}(\mathcal{B}_m) - \mathrm{freq}(\mathcal{B}_m)\right|, \end{aligned} \tag{18}$$

where TP/TN/FP/FN are the true/false positive/negative counts, y_i the labels, and $\mathcal{B}_m$ the m-th equal-width bin over $[0, 1]$ (mean confidence $\mathrm{conf}(\mathcal{B}_m)$ vs. observed toxic frequency $\mathrm{freq}(\mathcal{B}_m)$); ECE bins stayed fixed across models and datasets.

3 RESULTS AND DISCUSSION

3.1 Overall Predictive Performance on the Benchmark Test Sets

Using the OOF-frozen weight and threshold without dataset-specific retuning, GHXTox correctly classified 1,067 of 1,126 Test1 peptides (TP/TN/FP/FN = 287/780/26/33) and 551 of 582 strongly imbalanced Test2 peptides (35/516/20/11); the complete metric set is listed in Table 2. The low Test2 BACC (0.8618) and F1 (0.6931), despite high accuracy, reflect the difficulty of recovering the 46 toxic peptides and demonstrate why class-balanced and precision–recall metrics are essential for this benchmark.

Table 2 also reports previously published models on the same benchmark partitions (ToxMSRC and ToxPLTC; values transcribed from the original publications, and NR denotes an unreported metric) [2, 3]. GHXTox obtains the highest Test1 ACC, BACC, SP, MCC, AUROC, and AUPRC among the compared rows, whereas ToxPLTC has higher Test1 SN; on Test2, GHXTox obtains the highest ACC, SP, MCC, and reported AUPRC, but its BACC and SN remain below both reference models. This reflects a stronger overall balance of specificity, correlation, and positive-class ranking rather than comprehensive superiority on every metric. Because Test1 and Test2 were observed historically, these differences remain retrospective benchmark evidence and require confirmation on a new prefrozen external set.

Table 2: Performance comparison on the benchmark Test1 and Test2 sets.

Dataset	Model	ACC	BACC	SN	SP	MCC	AUROC	AUPRC
Test1	ToxMSRC	0.9405	0.9217	0.8781	0.9653	0.8520	0.9650	NR
	ToxPLTC	0.9378	0.9302	**0.9125**	0.9479	0.8496	0.9709	0.9426
	GHXTox (current)	**0.9476**	**0.9323**	0.8969	**0.9677**	**0.8705**	**0.9811**	**0.9674**
Test2	ToxMSRC	0.9416	0.8689	0.7826	0.9552	0.6550	0.9430	NR
	ToxPLTC	0.9261	**0.8804**	**0.8261**	0.9347	0.6197	0.9295	0.7353
	GHXTox (current)	**0.9467**	0.8618	0.7609	**0.9627**	**0.6673**	**0.9433**	**0.8046**

The final fused probabilities have Brier scores of 0.0410 and 0.0436 and ECE-10 values of 0.0196 and 0.0495 on Test1 and Test2, respectively. The Test2 AUPRC (0.8046) directly reflects the precision–recall trade-off for the rare toxic class, which AUROC does not capture, and the 11 false negatives on Test2 delineate the limits of the operating point: high specificity should not be interpreted as complete minority-class coverage. Discrimination and calibration curves are shown in Figure 3.




Figure 3: Overall discrimination and probability reliability of GHXTox. (A–C) Test1 ROC, precision–recall, and reliability curves. (D–F) Corresponding Test2 curves. The dashed precision–recall baselines denote class prevalence, while the reliability diagonals denote perfect calibration.

3.2 Complementarity of the 1D and 3D Experts

The two experts are fused only after independent probability generation. The 1D branch provides the stronger standalone ranking signal, whereas the 3D branch contributes confidence-weighted geometry and local chemical context. This separation makes the gain attributable to complementary probability evidence rather than duplicated use of an earlier fused prediction.

Table 3: Performance of the 1D probability streams and the current probability-level fusion. The final row for each benchmark uses the single-structure base output of the multi-source-trained structural checkpoint.

Dataset	Probability stream	AUROC	AUPRC	Brier
Test1	1D, uncalibrated	0.9799	0.9644	0.0445
	1D, OOF Platt calibrated	0.9799	0.9644	0.0429
	Current fusion (0.72/0.28)	**0.9811**	**0.9674**	**0.0410**
Test2	1D, uncalibrated	0.9409	0.7831	0.0491
	1D, OOF Platt calibrated	0.9409	0.7831	0.0451
	Current fusion (0.72/0.28)	**0.9433**	**0.8046**	**0.0436**




Figure 4: The 3D structural expert provides class-asymmetric corrections for a subset of errors made by the 1D sequence expert. (A) Distribution of Test1 and Test2 peptides among the both-correct, 1D-only-correct, 3D-only-correct, and both-wrong groups, defined using the standalone expert thresholds. (B) Conditional rescue rate of the 3D expert among all 1D errors and among toxic and non-toxic 1D errors. Structural rescue is concentrated primarily among non-toxic peptides on both benchmarks. (C) Prespecified effect-size estimates comparing 3D-only-correct with 1D-only-correct peptides for length, cysteine count, mean pLDDT, and chemical-site coverage; error bars denote 95% bootstrap intervals. None of the prespecified comparisons remained significant after Benjamini–Hochberg correction. Conformer availability is not shown as an independent explanatory variable because it is confounded with peptide length and structure-generator assignment.

Relative to the calibrated 1D probability stream, the final fusion modestly improves AUROC/AUPRC and lowers the Brier score on both benchmarks (Table 3), adding complementary structural ranking information while maintaining a lower probability error. The structural probability in these rows is the single-structure base output of the multi-source-trained structural checkpoint; no benchmark conformer cache is activated.

The 0.72 sequence weight is an empirical result of the training-OOF search, not a manually imposed assertion that sequence information is intrinsically more important. Both expert weights and the full-precision decision threshold of 0.47022256531284556 were fixed before Test1 or Test2 evaluation. The held-out benchmark results therefore assess one prespecified operating point; no benchmark-specific reweighting, threshold adjustment, or post hoc selection between equal and unequal fusion is performed.

The experts agreed on most benchmark peptides, but the discordant samples revealed a reproducible pattern of complementary error correction: the structural expert provided correct counter-evidence for more than one third of the sequence expert's errors (Figure 4B). This rescue was strongly class-asymmetric, with the structural expert mainly correcting false-positive predictions of the sequence expert, whereas improvements in toxic-peptide recall were limited. Peptides classified correctly only by the 3D expert also tended to be shorter, but none of the prespecified attribute comparisons remained significant after Benjamini–Hochberg correction, so this length pattern is descriptive rather than evidence that the structural expert is generally superior for short peptides. These results support a complementary rather than substitutive role for the structural expert (Figure 4).

3.3 Analysis of the Sequence and Structural Experts

The 1D expert is not the principal innovation of this work and is analyzed only briefly. Relative to the earlier pooled-ProtT5–TextCNN pipeline, the LoRA-adapted ProtT5 with bidirectional Mamba kept BACC and MCC broadly comparable on training OOF (0.9300 vs 0.9317 and 0.8562 vs 0.8586) while improving the ranking metrics (AUROC/AUPRC 0.9761/0.9533 vs 0.9724/0.9436), and OOF-fitted Platt calibration further reduced the Brier score on Test1 and Test2 (Table 4); the stronger ranking stream benefits the subsequent fusion with structural evidence (architecture in Section 2.3).

Table 4: Selected controlled comparisons for the task-adaptive 1D sequence expert. OOF architecture rows and benchmark calibration rows are reported separately and should not be compared across evaluation splits.

Evaluation	Variant	BACC	MCC	AUROC	AUPRC	Brier
Training OOF	Pooled ProtT5–TextCNN	0.9317	0.8586	0.9724	0.9436	NR
Training OOF	LoRA-ProtT5–Bi-Mamba	0.9300	0.8562	**0.9761**	**0.9533**	NR
Test1	Three-seed 1D, uncalibrated	–	–	0.9799	0.9644	0.0445
Test1	Three-seed 1D, OOF Platt	–	–	0.9799	0.9644	**0.0429**
Test2	Three-seed 1D, uncalibrated	–	–	0.9409	0.7831	0.0491
Test2	Three-seed 1D, OOF Platt	–	–	0.9409	0.7831	**0.0451**

Structure-quality analysis confirmed that pLDDT carries useful information: peptides with higher mean pLDDT generally exhibit stronger predictive performance, yet discarding low-confidence samples is not an optimal strategy, and continuous confidence down-weighting with gating is more robust. In parallel, a Cα-level residue graph compresses chemically complex side chains into single nodes, whereas a paired five-fold OOF experiment showed that adding the full-atom chemical-site residual to the frozen backbone improves BACC from 0.9153 to 0.9171 and MCC from 0.8312 to 0.8342 (Table 7, bottom rows), so multi-scale chemical information

provides additional discriminative power. Local geometric evidence is meaningful only in the appropriate sequence context: the same distance or hydrophobic contact can have different implications depending on residue identity and position, and the model therefore uses pLDDT-aware cross-attention to let sequence states selectively retrieve spatial evidence, with node- and peptide-level confidence gating controlling how much structural context is injected (mechanisms in Section 2.4).

A single predicted structure provides only one deterministic anchor, whereas short peptides may exhibit conformational heterogeneity. GHXTox compresses conformer ensembles into statistics and allows them to produce only a zero-initialized logit residual. On training OOF, activating the multi-source residual increased MCC from 0.87255 to 0.87445 (paired-bootstrap $\Delta = +0.00190$, 95% CI $[-0.00043, 0.00454]$, $p = 0.203$). Under the frozen test protocol, activating the residual on the covered records changed the metrics negligibly (Tables 5 and 6: Test1 MCC 0.8705 to 0.8726 and Test2 MCC 0.6673 to 0.6746, with about one prediction flip on each benchmark), which is consistent with the decision not to enable conformer statistics during benchmark inference; the bottleneck likely lies in mapping conformational variation to toxicity labels rather than in generating geometrically distinct conformers.

Table 5: Test1 multi-conformer ablation. Metrics of the frozen default predictor with the conformer residual disabled (zero-conformer baseline) and activated on the 486 covered records; both rows use the same checkpoint and the same full Test1 set.

Variant	ACC	BACC	MCC	AUROC	AUPRC	Brier
Base (zero conformer)	0.9476	0.9323	0.8705	0.9811	0.9674	0.0410
+ Conformer residual	0.9485	0.9329	0.8726	0.9811	0.9675	0.0407

Table 6: Test2 multi-conformer ablation. Metrics of the frozen default predictor with the conformer residual disabled (zero-conformer baseline) and activated on the 284 covered records; both rows use the same checkpoint and the same full Test2 set.

Variant	ACC	BACC	MCC	AUROC	AUPRC	Brier
Base (zero conformer)	0.9467	0.8618	0.6673	0.9433	0.8046	0.0436
+ Conformer residual	0.9485	0.8627	0.6746	0.9433	0.8043	0.0430

After combining all components, the 3D-v2 structural expert reached BACC, MCC, AUROC, and AUPRC values of 0.9208, 0.8464, 0.9711, and 0.9474 on Test1, compared with 0.9179, 0.8458, 0.9699, and 0.9426 for the historical Cα-only 3D-v1, a consistent but modest improvement; on Test2, AUPRC increased from 0.6969 to 0.7241 whereas MCC decreased from 0.6320 to 0.6128 (Table 7 and Figure 5). Finer-grained structural modeling therefore improves positive-class probability ranking but does not guarantee simultaneous gains in all metrics at a fixed operating point.

These ablation and comparison analyses are based on the frozen historical Test1 and Test2 benchmarks and are therefore retrospective evidence. Test2 contains only 46 toxic peptides, so SN, BACC, and MCC are sensitive to a few threshold-adjacent samples, which partly explains the dataset-dependent direction of the 3D-v2 gains; the multi-conformer test ablation used the archived test-side conformer cache (486 and 284 covered records on Test1 and Test2, with fixed source and sequence-matching policies) and activated the residual only on the covered subset, so its negligible effect should not be extrapolated as evidence that conformer information is useless.

Table 7: Ablation analysis of the 3D structural expert. The first four rows use historical benchmark predictions; the final two rows are a paired five-fold OOF chemical-site experiment.

Evaluation	Variant	BACC	MCC	AUROC	AUPRC
Test1	Historical Cα 3D-v1	0.9179	0.8458	0.9699	0.9426
Test1	pLDDT-aware multi-scale 3D-v2	**0.9208**	**0.8464**	**0.9711**	**0.9474**
Test2	Historical Cα 3D-v1	**0.8481**	**0.6320**	**0.9316**	0.6969
Test2	pLDDT-aware multi-scale 3D-v2	0.8453	0.6128	0.9295	**0.7241**
Training OOF	Frozen backbone, no chemical-site residual	0.9153	0.8312	0.9687	0.9388
Training OOF	Frozen backbone + chemical-site residual	**0.9171**	**0.8342**	**0.9692**	**0.9401**




Figure 5: Protocol-separated structural ablations. (A, B) Historical single-benchmark comparison of the Cα 3D-v1 and pLDDT-aware multi-scale 3D-v2 variants on Test1 and Test2. (C) Paired training-OOF comparison of the same frozen backbone without and with the chemical-site residual. Historical benchmark rows and paired OOF rows are not treated as one common statistical experiment.

3.4 Robustness, Statistical Uncertainty, and Applicability Analysis

Point estimates alone are insufficient for distinguishing a stable model improvement from variation caused by finite samples. We therefore use multi-seed averaging for the 1D expert and paired, sample-level bootstrap resampling for model comparisons, all performed on the frozen predictor without retraining, recalibration, or threshold adjustment. Three full-data 1D models (seeds 42, 123, and 2025) are averaged before calibration; this ensemble is the final predictor, with no seed selected according to Test1 or Test2 performance, and a 15-member fold-checkpoint ensemble was examined but not adopted because it did not improve the frozen validation criteria.

For risk-aware screening, prediction risk was quantified by the decision-boundary proximity $d_i = 1 - |p_i - \tau| / \max(\tau, 1-\tau)$ with $\tau = 0.47022256531284556$. On training OOF this proximity provides an informative ranking: as coverage decreases from 100% to 80%, accepted-sample error decreases and MCC increases monotonically, whereas equal-count random rejection shows no comparable improvement; at the prespecified 90% operating point the cutoff was frozen at $d^*_{\mathrm{OOF}} = 0.47361765874159856$ (Figure 6). Transferring this cutoff unchanged to Test1 and Test2 reduced the accepted-sample error by about 2.2–2.5 percentage points and improved MCC and BACC, while equal-count random rejection retained the full-coverage error (Table 8). The transfer uses no benchmark-specific quantile, coverage, class prevalence, or label, so the naturally different realized coverages reflect a single OOF-derived cutoff rather than retuned abstention rates. This supports a risk-aware screening workflow in which boundary-proximal predictions are flagged for review, although it does not constitute independent validation, and the original binary prediction remains available for every abstained peptide.

Table 8: The OOF-frozen selective policy identifies lower-risk accepted subsets on both established benchmarks. Random-rejection values are means over 5,000 masks with the same accepted count as the frozen policy. The binary probabilities, fusion rule, and decision threshold are unchanged.

Dataset	Method	Coverage (%)	Error (%)	MCC	BACC	SN	SP
Test1	Full binary prediction	100.00	5.24	0.8705	0.9323	0.8969	0.9677
	Frozen selective prediction	88.54	2.71	0.9329	0.9629	0.9397	0.9860
	Equal-count random rejection	88.54	5.24	0.8705	0.9323	0.8969	0.9677
Test2	Full binary prediction	100.00	5.33	0.6673	0.8618	0.7609	0.9627
	Frozen selective prediction	86.94	3.16	0.7781	0.8983	0.8158	0.9808
	Equal-count random rejection	86.94	5.33	0.6670	0.8617	0.7607	0.9627

3.5 Interpretability and Representative Case Studies

The interpretation experiments used a prespecified case-selection rule: within each test set and each expert-outcome group, one toxic and one non-toxic peptide nearest the fusion threshold were chosen (ties resolved by source index), forming a 16-peptide cohort. Before perturbation, baseline probabilities were recomputed and compared with the stored prediction vectors; the maximum absolute discrepancy for the 1D expert within the case cohort was 3.45×10^{-4}, and the corresponding 3D discrepancies were 5.49×10^{-4} on Test1 and 1.14×10^{-5} on Test2, none of which changed any decision. The interpretation analyses therefore describe model sensitivity on the frozen predictor rather than confirmed biological mechanisms.

Mean pLDDT was strongly associated with the learned global structural gate (Spearman 0.960 on Test1, 0.950 on Test2, pooled 0.957), which can be read as the model preferring to trust structural evidence when the predicted structure is more confident, systematically down-weighting structural evidence for flexible or disordered short peptides, consistent with their conformational heterogeneity. Across 445 individual site deletions, most changes were small (median 0.00048, mean 0.00997, 95th percentile 0.057, maximum 0.2994 in p_{3D}); hydrophobic

FIGURE PLACEHOLDER — to be drawn by co-author
Selective prediction (A/B): OOF risk–coverage vs. random rejection

FIGURE PLACEHOLDER — to be drawn by co-author
Selective prediction (C/D): frozen-threshold transfer on Test1/Test2

Figure 6: OOF-frozen decision-boundary proximity identifies lower-risk accepted subsets and transfers without benchmark-specific tuning. (A) Accepted-sample error and (B) MCC across 100%, 95%, 90%, 85%, and 80% coverage on group-aware training OOF predictions. The frozen uncertainty ranking is compared with equal-count random rejection, and the vertical dashed line marks the prespecified 90% OOF operating point used to obtain the fixed cutoff. Shaded regions denote 95% intervals from 5,000 label-stratified paired-bootstrap replicates. (C, D) Full-coverage, equal-count random-rejection, and frozen-policy performance on Test1 and Test2 at the naturally realized benchmark coverages. No benchmark-specific quantile was recomputed, and benchmark labels were accessed only after the accept/abstain decisions had been generated, solely for evaluation.

and aromatic sites showed the largest mean effects (0.126 and 0.0687, respectively) and sulfur-containing sites the smallest (0.00179), suggesting that hydrophobic patches and aromatic interactions (aromatic stacking, cation–π) may be among the more informative spatial-chemical features for peptide toxicity, consistent with the prevalence of hydrophobic and aromatic residues in membrane-active or toxic peptides (a hypothesis requiring experimental validation). The opposing directions of the largest deletion effects (Phe8 increased p_{3D}, Pro19 decreased it) show that deletion scores depend on the surrounding peptide context and cannot be read as an intrinsic toxicity label for a functional group (Figure 7).

Fixed late fusion agreed on most benchmark peptides, and the discordant cases illustrate its operational consequences (the aggregate pattern is reported in Section 3.2). The toxic peptide `sequence_23_23` (ACLDIGNSCRED, two cysteines) had a weak 1D probability of 0.2806 but a high-confidence 3D probability of 0.9954; fusion raised the probability to 0.4808 and restored the correct toxic classification, suggesting that the toxicity signal of this short peptide may depend more on spatial conformation and the cysteine backbone than on linear sequence features. The toxic peptide `sequence_34_34` had a correct 1D probability of 0.5447 but a 3D probability of 3×10^{-5}, and fusion reduced the probability to 0.3922, producing a false negative; strong sequence evidence can therefore be overridden when the structural expert supplies sufficiently strong opposing evidence, and such single-sample evidence conflicts warrant further inspection (Figure 8). These cases confirm the design premise of the model: peptide toxicity depends not only on the linear sequence but also on three-dimensional conformation as a key source of evidence, with the two types of evidence sometimes consistent and sometimes conflicting; fixed late fusion lets the two dimensions complement each other, which is why the 1D sequence and 3D conformation are placed together and fused at the probability level rather than relying on a single dimension.




Figure 7: Structural-confidence and chemical-site sensitivity analysis. (A) Association between mean pLDDT and the global gate. (B) Distribution of within-peptide pLDDT–node-gate correlations. (C) Comparison of the eight modeled chemical categories. (D) Largest probability-increasing and probability-decreasing site-deletion effects. The deletion panels use the 3D expert and calculate Δp_{fused} with p_{1D} fixed; the reported values denote model sensitivity, not experimentally verified toxicophores.




Figure 8: Representative disagreements show that fixed late fusion can either rescue an expert-specific error or override an otherwise correct prediction. (A) A peptide for which the 3D expert restores a toxic decision missed by the 1D expert. (B) A peptide for which opposing structural evidence reverses a correct 1D prediction. Bars show the 1D, 3D, and fused probabilities against the frozen fused decision threshold. These examples demonstrate operational complementarity and failure modes rather than a causal biological mechanism.

3.6 Limitations and Future Directions

The most fundamental limitation stems from the single-output nature of three-dimensional conformation prediction. Short peptides in solution typically populate multiple interconverting conformations, and toxicity is usually mediated by one particular conformation or class of conformations; a single predicted structure cannot cover this multimodal distribution. This is precisely why the project introduced multiple conformation generators (PepFlow and AlphaFold2/ColabFold, assigned by length range). However, different generators exhibit inherent noise, and normalizing conformers across models and sources further amplifies this inconsistency: activating the multi-conformer residual on the test sets produced negligible and inconsistent effects that did not justify a public inference protocol, and source-independent and fusion-aware candidates also failed their prespecified retention gates (Section 3.3, Tables 5 and 6), so the conformer residual was eventually disabled for benchmark and public inference and the structural information-extraction capacity of the model was not fully released. On training OOF the residual improved MCC by only +0.00190 ($p = 0.203$, not significant), and expanding the conformer cohort from 250 to 761 peptides did not pass the retention gates because the added records were all negative. In addition, full-atom conformational sampling (e.g., PepFlow) is computationally far more expensive than single-structure prediction, which limited large-scale generation and deployment. We therefore hope that next-generation protein structure prediction models can provide, at acceptable computational cost, multiple possible conformations and their probabilities (for example, lightweight multi-conformer sampling based on flow matching or diffusion), more closely matching the multimodal nature of peptide conformation and potentially further releasing the value of conformational information in toxicity prediction.

The second limitation is that the 1D sequence and 3D conformation dimensions are combined with a fixed 0.72/0.28 weight rather than dynamically adjusted per sample. This may partly stem from the first limitation: the inherent noise among different conformation predictors masks the information that would indicate which dimension should be trusted for a given sample, and when structural evidence is itself inconsistent across generators, the model cannot reliably distinguish, per sample, the reliability of sequence evidence from that of conformational evidence and therefore falls back to fixed weights. Consistent with this, sample-level confidence gates and dynamic routing attempts did not pass the retention gates: the former produced MCC values below the fixed default, and the latter improved ranking and calibration but did

not exceed the frozen default's decision metrics (Section 3.4). This reflects that the two dimensions have not yet achieved sufficiently effective information complementarity; adaptive and interpretable fusion based on evidence reliability, together with more consistent conformational evidence sources, are directions for future work.

4 CONCLUSIONS

GHXTox explores the complementary joint use of sequence and conformational evidence by combining a task-adaptive LoRA-ProtT5–Bi-Mamba sequence expert with a pLDDT-aware multi-scale structural expert through probability-level fusion; the two experts are independent and their complementarity is characterized by the structural expert correcting a subset of sequence errors in a class-asymmetric way (Section 3.2). The structural expert integrates residue geometry, full-atom-derived chemical sites, and sequence-conditioned structural evidence, while multi-conformer information is restricted to training and controlled ablation. The final predictor uses the structural expert's single-structure base probability. The 1D/3D weights (0.72/0.28) and the decision threshold (0.47022256531284556) were fixed from training OOF predictions before benchmark evaluation.

On the frozen historical Test1 and Test2 benchmarks, the model reaches MCC values of 0.8705 and 0.6673 and AUPRC values of 0.9674 and 0.8046, and the final fusion improves AUROC, AUPRC, and the Brier score relative to the calibrated 1D stream. The 3D expert correctly classified 36.92% and 37.50% of the respective Test1 and Test2 errors made by the 1D expert, with most of these structural rescues occurring among non-toxic peptides. An OOF-frozen selective policy further reduced accepted-sample error to 2.71% and 3.16% at realized coverages of 88.54% and 86.94%, respectively, without benchmark-specific cutoff selection. Conformer-derived information produced only modest and non-uniform improvements, indicating that mapping conformational variation to toxicity-relevant evidence remains an important limitation. The interpretability analyses describe model sensitivity rather than causal mechanisms.

Several limitations remain, most notably the single-output nature of conformation prediction and the fixed probability-level fusion between the two dimensions, as discussed in Section 3.6; both benchmarks were also observed during earlier model development, and the structures are predicted rather than experimental. Looking ahead, we hope that more powerful three-dimensional conformation models, capable of producing multiple conformations with their probabilities at acceptable computational cost, together with dynamic, evidence-reliability-aware fusion between the sequence and structural dimensions, will enable a deeper complementary joint use of the two types of information, with experimental validation where feasible.

Data and Software Availability

The source code, configuration files, fold manifests, and inference scripts used in this study are available at `https://github.com/Suiyumanbu/GHXTox`. A versioned archival release containing the exact commit identifier, environment manifest, frozen model parameters, calibration coefficients, fusion weights, full-precision decision threshold, and sample-level prediction files will accompany the final publication. Raw peptide records were obtained from the public databases described in Section 2.1. Where redistribution is restricted by the original database terms, accession lists and preprocessing scripts are provided instead of redistributing the source records.

CRediT Authorship Contribution Statement

Acknowledgements

Declaration of Competing Interest

The authors declare that they have no known competing financial interests or personal relationships that could have appeared to influence the work reported in this paper.

References

[1] Markus Muttenthaler, Glenn F. King, David J. Adams, and Paul F. Alewood. Trends in peptide drug discovery. *Nature Reviews Drug Discovery*, 20(4):309–325, 2021.

[2] Shengli Zhang, Jingyi Ren, and Yunyun Liang. An innovative peptide toxicity prediction model based on multi-scale convolutional neural network and residual connection. *Bioinformatics*, 41(10):btaf462, 2025.

[3] Yunyun Liang and Chenxia Wang. ToxPLTC: Peptide toxicity prediction by integrating a pre-trained T5 protein language model and text convolutional neural network. *Journal of Chemical Information and Modeling*, 66(7):4058–4074, 2026.

[4] Jiahui Guan, Peilin Xie, Dian Meng, Lantian Yao, Dan Yu, Ying-Chih Chiang, Tzong-Yi Lee, and Junwen Wang. ToxiPep: Peptide toxicity prediction via fusion of context-aware representation and atomic-level graph. *Computational and Structural Biotechnology Journal*, 27:2347–2358, 2025.

[5] Duong Thanh Tran, Nhat Truong Pham, Nguyen Doan Hieu Nguyen, Leyi Wei, and Balachandran Manavalan. HyPepTox-Fuse: An interpretable hybrid framework for accurate peptide toxicity prediction fusing protein language model-based embeddings with conventional descriptors. *Journal of Pharmaceutical Analysis*, 15(8):101410, 2025.

[6] Yanling Wang, Na Li, Xiao Wang, Feng Cao, Shuwen Xiong, and Leyi Wei. Integrating protein language models and geometric deep learning for peptide toxicity prediction. *Journal of Chemical Information and Modeling*, 65(14):7800–7810, 2025.

[7] Shihu Jiao, Xiucai Ye, Tetsuya Sakurai, Quan Zou, Wu Han, and Chao Zhan. Integration of pre-trained protein language models with equivariant graph neural networks for peptide toxicity prediction. *BMC Biology*, 23:229, 2025.

[8] Ahmed Elnaggar, Michael Heinzinger, Christian Dallago, et al. ProtTrans: Toward understanding the language of life through self-supervised learning. *IEEE Transactions on Pattern Analysis and Machine Intelligence*, 44(10):7112–7127, 2022.

[9] Edward J. Hu, Yelong Shen, Phillip Wallis, Zeyuan Allen-Zhu, Yuanzhi Li, Shean Wang, Lu Wang, and Weizhu Chen. LoRA: Low-rank adaptation of large language models. In *International Conference on Learning Representations*, 2022.

[10] Albert Gu and Tri Dao. Mamba: Linear-time sequence modeling with selective state spaces. In *Conference on Language Modeling*, 2024.

[11] Zeming Lin, Halil Akin, Roshan Rao, Brian Hie, Zhongkai Zhu, Wenting Lu, et al. Evolutionary-scale prediction of atomic-level protein structure with a language model. *Science*, 379(6637):1123–1130, 2023.

[12] John Jumper, Richard Evans, Alexander Pritzel, et al. Highly accurate protein structure prediction with AlphaFold. *Nature*, 596:583–589, 2021.

[13] Milot Mirdita, Konstantin Schütze, Yoshitaka Moriwaki, et al. ColabFold: Making protein folding accessible to all. *Nature Methods*, 19(6):679–682, 2022.

[14] Osama Abdin and Philip M. Kim. Direct conformational sampling from peptide energy landscapes through hypernetwork-conditioned diffusion. *Nature Machine Intelligence*, 6(7):775–786, 2024.

[15] Shengli Zhang and Xinyi Zhang. NeuroPpred-PSCG: A multimodal framework using ProtT5 and structural features for neuropeptide prediction based on gated cross-attention mechanism and multiscale gated convolution. *Journal of Chemical Information and Modeling*, 2026.

[16] Shihu Jiao, Xiucai Ye, Tetsuya Sakurai, Quan Zou, and Ran Liu. Integrated convolution and self-attention for improving peptide toxicity prediction. *Bioinformatics*, 40(5):btae297, 2024.

[17] Vitali Morozov, Carlos H. M. Rodrigues, and David B. Ascher. CSM-Toxin: A web-server for predicting protein toxicity. *Pharmaceutics*, 15(2):431, 2023.

[18] Nishu Sharma, Leimarembi Devi Naorem, Shilpi Jain, and Gajendra P. S. Raghava. ToxinPred2: An improved method for predicting toxicity of proteins. *Briefings in Bioinformatics*, 23(5):bbac174, 2022.

[19] Lesong Wei, Xiucai Ye, Yuyang Xue, Tetsuya Sakurai, and Leyi Wei. ATSE: A peptide toxicity predictor by exploiting structural and evolutionary information based on graph neural network and attention mechanism. *Briefings in Bioinformatics*, 22(5):bbab041, 2021.

[20] The UniProt Consortium. UniProt: A worldwide hub of protein knowledge. *Nucleic Acids Research*, 47(D1):D506–D515, 2019.

[21] Limin Fu, Beifang Niu, Zhengwei Zhu, Sitao Wu, and Weizhong Li. CD-HIT: Accelerated for clustering the next-generation sequencing data. *Bioinformatics*, 28(23):3150–3152, 2012.

[22] Akanksha S. Rathore, S. Choudhury, A. Arora, P. Tijare, and Gajendra P. S. Raghava. ToxinPred 3.0: An improved method for predicting the toxicity of peptides. *Computers in Biology and Medicine*, 179:108926, 2024.

[23] John C. Platt. Probabilistic outputs for support vector machines and comparisons to regularized likelihood methods. In Alexander J. Smola, Peter L. Bartlett, Bernhard Schölkopf, and Dale Schuurmans, editors, *Advances in Large Margin Classifiers*, pages 61–74. MIT Press, Cambridge, MA, 1999.

[24] Alican Gulsevin and Jens Meiler. Benchmarking peptide structure prediction with AlphaFold2. *bioRxiv*, 2022.

[25] Víctor Garcia Satorras, Emiel Hoogeboom, and Max Welling. $E(n)$ equivariant graph neural networks. In *Proceedings of the 38th International Conference on Machine Learning*, volume 139 of *Proceedings of Machine Learning Research*, pages 9323–9332, 2021.

[26] Kaiming He, Xiangyu Zhang, Shaoqing Ren, and Jian Sun. Deep residual learning for image recognition. In *Proceedings of the IEEE Conference on Computer Vision and Pattern Recognition (CVPR)*, pages 770–778, 2016.

[27] Ashish Vaswani, Noam Shazeer, Niki Parmar, Jakob Uszkoreit, Llion Jones, Aidan N. Gomez, Lukasz Kaiser, and Illia Polosukhin. Attention is all you need. In *Advances in Neural Information Processing Systems*, volume 30, pages 5998–6008, 2017.

[28] Ilya Loshchilov and Frank Hutter. Decoupled weight decay regularization. In *International Conference on Learning Representations*, 2019.

[29] Brian W. Matthews. Comparison of the predicted and observed secondary structure of T4 phage lysozyme. *Biochimica et Biophysica Acta (BBA) – Protein Structure*, 405(2):442–451, 1975.

[30] Glenn W. Brier. Verification of forecasts expressed in terms of probability. *Monthly Weather Review*, 78(1):1–3, 1950.

[31] Bradley Efron and Robert J. Tibshirani. *An Introduction to the Bootstrap*. Chapman and Hall/CRC, New York, 1993.

[32] Markus Ojala and Gemma C. Garriga. Permutation tests for studying classifier performance. *Journal of Machine Learning Research*, 11:1833–1863, 2010.